

**Attachment
MRCA Item IV(a)
September 20, 2007**

Materials prepared by: C. McLane, 9/18/07

ATN: Elizabeth Jordon
 L.A. River Center & Gardens
 570 West Ave 26th St. Suite 100
 Los Angeles, CA 90065

323.221.8900 ext. 186 O
 F

Elizabeth.jordon@mrca.ca.gov

Terms: Valid for 15 days

Representative: Philip Castiglia

Date: 8/30/07

PROPOSAL AND AGREEMENT

This proposal is valid for 15 days

As per site visit on 8/28/07

Tujunga Wash Scope of Work (Prevailing wage)

- 1) Installation of four bike racks at points indicated on plans. Bike racks shall be provided by MRCA and installed per manufacturer's specifications. **\$1,885.00**
- 2) Installed of two trash cans at the seating areas at Victory and Coldwater Canyon, as indicated on the plans. Trash cans shall be provided by MRCA and installed per manufacturer's specifications. **\$750.00**
- 3) Removal and replacement of two bollards at the Coldwater Canyon entrance. Bollards shall be installed at point indicated on plans. Bollards shall be installed per the attached detail.
Existing Bollards to be removed with footings and placed back into new location with new added concrete footing. \$2,750.00
- 4) Removal of seven existing interpretive displays. Concrete area around base of display shall be cut. New displays, provided by MRCA, shall be installed per the attached detail. All concrete cuts shall be smooth and straight. New concrete shall match existing concrete as close as possible. **\$ 5,235.00**
- 5) Cleaning and repair of existing concrete block retaining wall. The wall is approximately 42' x 8' and needs to be sandblasted and patched so that it can have tile applied. The tile application will be performed by a local arts group and should not be included in the cost. Photos of the wall are attached. **\$1,675.00**
- 6) Purchase and Plant 250-24 inch box Platanus Racemosa (mixture of low branching and standards) with amendments, plant tablets, and to be staked. All excess soil to be used around each tree for the water basin. No soil export. Bid includes tractor ingress and egress. No irrigation included. **\$72,750.00**
- 7) Plant 5000-one gallon perennials provided by MRCA. All plants to be delivered to site and Terra Form Inc. to unload and distribute around site. All plants to be installed with amendments and

plant tablets. All excess soil to be used around each plant for water basin. No soil export. Bid includes tractor ingress and egress. **\$49,320.00**

General Notes:

No permits, No soil or structural engineer work included, No soil export included. Any unforeseen obstacles during trenching, grading, or excavating that hinder work progress are not included in pricing. This may include but not limited to rocks, abandoned footings, underground utilities, abandoned grave site, toxic chemicals, artifacts, fossils or endangered species habitat, etc., and will be deemed an extra. Concrete removal to four inches of thickness with no rebar or wire mesh included. Concrete with wire mesh or rebar will be an extra charge to remove. Toilet by Owner or provided by Terra Form at a rate of \$141.00 per month. Bid is valid for fifteen days due to material costs increasing more than the average annual rate. Water to be made available by the MRCA for tree and shrub planting.

Accepted by: _____ **Date** _____